



# PRE-INSTALLATION TEST KIT



Le

Technology

Now you can survey any potential site to certify the RF communication link between the EAC panel and the Wyreless Access peripheral devices from their planned installed locations. The test kit has a MRL Tester Unit which is used to check out all interior and exterior doors, gate and elevator installations, moveable checkpoints and guard tour applications. The kit comes in a carrying case for easy portability.

The test kit is self-contained, portable and requires only a few minutes to check each location. The Test Panel Interface Module is located where its equivalent Panel Interface Module will be installed. The MRL Tester is held where the Wyreless Access peripheral device will be installed or used. A Link switch is pressed initiating the communication checkout process. During "Linking" 16,000 bits are transmitted and received twice at less than half-power and then are compared. Over 99% of all messages must be correctly transmitted and received before an "acceptable" indication is given. If the "acceptable" signal is given, the communications were greater than 99% accurate using less than half the power that will be used during normal operation of the device that will be installed.

## ORDER INFORMATION

### **TK797**

- Test Panel Interface Module
- Test MRL